



Mile End Hospital, London

Client: Enfield Council

A.C. Preou were asked to replace the air-cooled chiller at the rear of the laundry area. Water samples proved the system had been poorly maintained, which had resulted in corroded pipework, and unit failure.

Our works involved:

- Making safe, draining and disconnecting the existing unit from the water and electrical supplies.
- Extend the concrete base to suit the new unit.
- Crane in the new unit, connect pipework and controls
- Clean and red oxide existing pipework
- Dose water treatment, to ensure the longevity of the system.
- Commission unit

The system was back online, ready to keep the hospital cool during the hot summer.

